



Project / Job Name: _____

Location: _____

Fixture Type: _____

Notes: _____

62-1800 - 7 inch; LED Disk Light; 6 Unit Contractor Pack; 5-CCT Selectable 27K/3K/35K/4K/5K; White Finish



GENERAL

| | |
|---------------------------|-----------------------------------|
| Company | NUVO |
| EA Height | 10.03 |
| EA Width | 7.67 |
| EA Length | 7.67 |
| Bulb Included | Integrated |
| Diameter | 7.42 |
| Material | Steel |
| Fixture Type | Disk Light |
| Status | Active |
| Style | Contemporary |
| Surge Protection | Built-in surge protection - 2.5KV |
| CCT Selectable | Yes |
| Wattage Selectable | No |
| Finish Family | White |
| Amps | 0.125A |
| Has Camera | No |
| IOT Enabled | No |
| Lens Finish | White |
| Lens Material | Acrylic |
| Power Factor | 0.9 |
| SDS Class | LED_Fixture |
| Sloped Ceiling Compatible | Yes |
| Indoor Outdoor | Indoor |
| Product Technology | LED |
| Incandescent Equivalent | 60W |

ELECTRICAL

| | |
|---------------------|-------------------------------|
| CCT (Kelvin Temp) | 2700K/3000K/3500K/4000K/5000K |
| Dimmable | Yes-Dimmable |
| Hours Rated | 50000 |
| Beam Angle (degree) | 110 |
| Color Temp | Warm to Cool White |
| CRI | 90+ |
| Dimming Type | 120V only, Phase cut |
| Operating Frequency | 60Hz |
| Operating Temp | -13F to +104F (-25C to +40C) |
| Lumens | 930L-1000L |
| Volts | 120v |
| Watts | 15W |

PHYSICAL

| | |
|---------------|----------------|
| Lamp Base | Integrated |
| Finish | WHITE |
| ANSI Base | Integrated |
| Lamp Type | Integrated LED |
| Fixture Shape | Round |

ADDITIONAL INFO

| | |
|--------------------|---------------|
| Warranty | 5-Years |
| Installation Notes | Keyhole Slots |

PACKAGING

| | |
|---------------|----------------|
| UPC | 045923625855 |
| Case Cube | 1.5629 |
| Case Height | 10.629 |
| Case Length | 15.94 |
| Case Quantity | 4 |
| Case UPC | 10045923625852 |
| Case Weight | 19.581 |
| Case Width | 15.94 |
| EA Cube | 0.3415 |
| EA Height | 10.03 |
| EA Length | 7.67 |
| EA Quantity | 1 |
| EA Weight | 4.497 |
| EA Width | 7.67 |
| Pack Type | Contractor Box |
| Web Height | 1.42 |
| Web Width | 7.42 |

COMPLIANCE

| | |
|-----------------------|-----------------------|
| CA Prop 65 | Lead |
| FCC Compliant | Yes |
| Location Rating | Wet |
| NSF Approved | No |
| ROHS Compliant | Yes |
| Safety Listing | cETLus - Listed |
| California Ban | California T24 Listed |
| DLC Approved | No |
| Energy Star Certified | No |
| Title 20 | Exempt |
| T24/JA8 Compliant | Yes |