Project / Job Name:

Location:

Fixture Type:

Notes:



62-5901 - 6 Watt LED Landscape Floodlight; RGB and 2700K-5000K Tunable White; Bronze Finish

WET LOCATION | 90+ CRI | DIMMABLE | ETL US | FC | RoHS COMPLIANT | CCT SELECTABLE | 50,000 HOURS | 60° BEAM | 5 YEAR WARRANTY | 120 VOLT | IP 65

GENERAL

Company	NUVO
EA Height	4.72
EA Width	3.39
EA Length	6.02
Bulb Included	Integrated
Starfish Communication Protocol	WiFi-2.4GHz
Diameter	2.45
Material	Die-cast Aluminum
Fixture Type	Flood Light
Includes	Die-Cast Mounting Plate
Status	Active
Style	Utility
Surge Protection	Built-in surge protection - 1KV
Total Harmonic Distortion	<20%
Starfish Voice Assistants Supported	Alexa, Google Home, Siri, SmartThings
CCT Selectable	Yes
Wattage Selectable	No
Finish Family	Bronze
Amps	0.050A
Has Camera	No
IOT Enabled	Yes
Lens Material	Acrylic
Lensed	Yes
Power Factor	>0.5
SDS Class	LED_Fixture
Starfish Software Supported	Tuya/Starfish App
Indoor Outdoor	Outdoor
Product Technology	LED
Incandescent Equivalent	45W
Serviceable Battery	No
Battery Indicator	No
Digital Display	No

ELECTRICAL

CCT (Kelvin Temp)	2700K-5000K
Dimmable	Yes-Dimmable
Hours Rated	50000
Beam Angle (degree)	60
Color Temp	RGB and Tunable White
CRI	90+
Dimming Type	Smart-Starfish App only
Operating Frequency	60Hz
Operating Temp	-4F to +104F (-20C to +40C)
Lumens	480L
Volts	120v
Watts	6W

PHYSICAL

Lamp Base	Integrated
Finish	BRONZE
ANSI Base	Integrated
Lamp Type	PAR16
Mounting Procedure	Pole/Post/Plate

ADDITIONAL INFO

Warranty	5-Years

PACKAGING

UPC	045923623615
Case Cube	0.5318
Case Height	7.48
Case Length	18.9
Case Quantity	12
Case UPC	10045923623612
Case Weight	10.05
Case Width	6.5
EA Cube	0.0557
EA Height	4.72
EA Length	6.02
EA Quantity	1
EA Weight	0.77
EA Width	3.39
Pack Type	Box
Web Height	3.25
Web Length	5.5
Web Width	2.45

COMPLIANCE

CA Prop 65	Lead
FCC Compliant	Yes
IP Rating	IP65
Location Rating	Wet
ROHS Compliant	Yes
Safety Listing	cETLus - Listed
California Ban	Lawful for sale
Title 20	Exempt
T24/JA8 Compliant	No

© Satco Products, Inc.
All rights reserved 2026